



METROPOLITAN  
TRANSPORTATION  
COMMISSION

Joseph P. Bort MetroCenter  
101 Eighth Street  
Oakland, CA 94607-4700  
Tel: 510.464.7700  
TDD/TTY: 510.464.7769  
Fax: 510.464.7848

## *Memorandum*

TO: Partnership Technical Advisory Committee

DATE: April 9, 2007

FR: Raymond Kan and Carolyn Clevenger

RE: Report on Transportation 2030 Plan's Key Measures of Progress

As part of Transportation 2030 Plan, MTC committed to report on the Key Measures of Progress for the six goals – safety and maintenance, reliability, access, livable communities, clean air, and efficient freight travel. The Key Measures of Progress are meant to help MTC evaluate the degree to which its actions, guided by the policies developed in Transportation 2030 Plan, have advanced the plan's goals, and to provide insight as we move forward with the 2009 Regional Transportation Plan (RTP). These measures will either be carried over into the next RTP, modified, or deleted depending on their effectiveness in measuring progress, availability of data, and consistency with the goals and objectives developed for the 2009 RTP.

The six Transportation 2030 goals and its associated objectives and key measures of progress are highlighted in the attached Transportation 2030 Goals' Measures of Progress Report. MTC staff has prepared this report to document progress made in these key measures between the base year, roughly the time of the adoption of the Transportation 2030 Plan (2004), and now, using the most recent data available (typically 2005 or 2006). Much of the data and analysis represented in this report, particularly in the Safety and Reliability sections, is also done for the annual State of the System put together by MTC and Caltrans District 4. As we move forward, MTC staff will evaluate how the Key Measures of Progress reflect on the effectiveness of RTP's programs/projects in carrying out Commission policy.

Given the short time period covered by this data, trend lines for most measures will be difficult if not impossible to determine. MTC staff therefore recommends that we continue to monitor these key measures, in addition to those suggested below, as we proceed with implementation of the next RTP.

### Proposed Changes to Key Measures of Progress for 2009 RTP

Based on the assessment of the Transportation 2030 goals' key measures of progress, MTC proposes to carry, modify, or delete certain key measures of progress based on their effectiveness in measuring progress, availability of data, and consistency with the goals and objectives to be developed for the 2009 RTP. Table 1 presents the suggested actions and reasons for suggested actions for each key measure of progress.

**Table 1. Proposed Changes to Key Measures of Progress**

Existing Measure	Suggested Action	Reasons for Action
<b>SAFETY: A Safe and Well-Maintained System</b>		
Number of injuries and fatalities at identified safety “hot spots”	Modify: 1. Number of injuries and fatalities in the region 2. Number of collisions involving fatalities or injuries by mode, cause, and facility type	“Hot spots” are not currently tracked and make up <1% of collisions at major intersections when MTC conducted a sampling of collision data.
Progress in completing bridge seismic retrofit program	Move to new SECURITY goal.	More appropriately placed in a new SECURITY goal.
Pavement condition Index (freeways and roads)	No change	
Average age of transit fleet	Modify: 1. Average age of transit fleet by service vehicle type mode 2. Miles between service calls by operator/vehicle type	To track the reliability of the service as vehicles either age or conversely, get younger.
Progress in completing bridge seismic retrofit program	Move to new SECURITY goal.	More appropriately placed in a new SECURITY goal.
<b>RELIABILITY: A Reliable Commute</b>		
Capacity added to the Metropolitan Transportation System (MTS)	Modify: 1. Progress in completing the HOV/HOT network. 2. Progress in implementing Regional Measure 2 and Resolution 3434 transit expansion projects. 3. Number of vehicle revenue miles added to the transit system.	1. The MTS is no longer being used. The new HOV measure will provide insight into a priority component of the roadway network that MTC is focused on expanding. 2. RM2 and 3434 are the region’s priority transit expansion projects, and monitoring their progress is a good barometer for added transit capacity. 3. Monitoring vehicle revenue miles will provide a more detailed description (by mode) of transit service capacity with less reliance on assumptions made by the regional model.
Levels of service in congested corridors	Modify: Levels of service and delay in congested corridors	
Progress with freeway ramp meters and traffic signal retiming	Modify: Progress with implementing freeway ramp metering and traffic signal retiming	
On-time transit	No change	

Existing Measure	Suggested Action	Reasons for Action
performance		
Effectiveness of incident management strategies	Modify: Effectiveness of freeway incident management strategies	
New transit connectivity projects	No change	This measure may move to the ACCESS goal as the new RTP Goals are developed.
Progress in improving traveler information	Progress in improving traveler information such as providing real-time transit information, personalized 511 services, and increased public awareness of the 511 traveler system	
<b>ACCESS: Access to Mobility</b>		
Amount of Lifeline transportation service provided	No change	
Progress in implementing transportation programs for older adults	Modify: Progress in implementing strategies from the Coordinated Public Transit/Human Services Transportation Plan	The Coordinated Plan addresses strategies for older adults, the disabled, and the people with limited incomes
Progress in completing community-based plans	Delete	
MTC and transit operator Title VI reports	Delete	MTC and transit operators, as Federal grantees, are legally required to prepare Title VI reports. Typically, no findings of significance come from these reports. In addition, MTC has in place a discrimination complaint process to address customer complaints.
NEW: Progress in implementing improvements in wayfinding signage and in-station information at regional transit hubs		

Existing Measure	Suggested Action	Reasons for Action
<b>LIVABLE COMMUNITIES: A Region of Vibrant Communities</b>		
Number of TLC projects completed	Modify: Number of regional and county TLC capital projects funded and completed.	This measure focuses on the delivery of capital projects.
Number of new Transit Oriented Development projects assisted with HIP	Modify: Number of new housing projects assisted with Regional HIP.	Only two CMAs have a county HIP program.
Number of new mixed use development projects assisted with HIP	Delete	By definition all HIP projects are transit-oriented, whereas mixed-use is not a critical criterion for HIP grants.
Annual results of T-Plus program	Delete	MTC staff already prepares a separate annual evaluation of the T-Plus program.
NEW: TOD Policy Implementation (Progress in implementing MTC's TOD Policy as applied to Resolution 3434 projects)	Examples: Number of Resolution 3434 expansion stations with station area plans  Number of Resolution 3434 corridors meeting TOD policy thresholds  Number of housing units planned close to transit stations and in downtowns  Number of housing units in the ground (permitted) that are close to transit stations and in downtowns  Mode share for residents near transit based on 2010 BATS data	Measures progress in implementing the Resolution 3434 TOD Policy
NEW: Progress in implementing FOCUS Priority Development Areas	Examples:  Planned and constructed housing units within adopted PDAs  Mode share for residents near transit based on 2010 BATS data	Anticipate adoption of Priority Development Areas and the need to measure their progress.

Existing Measure	Suggested Action	Reasons for Action
NEW: Access to High Quality Transit Service	Percent of all residents in the urban core who are within a 5-minute walk (or equivalent distance) to 10-minute or better transit service	Measures residents' proximity to high quality transit service. It could be extended to employees and Priority Development Areas.  Additional analytic measures could be developed to fully assess transit service quality (e.g., route directness, hours of service spans).
NEW: Transit Ridership	Number of boardings per capita	New measure to gauge the market of transit customers as the region continues to grow.
<b>CLEAN AIR: Clearing the Skies</b>		
Periodic analysis of consistency between the Transportation 2030 Plan and Transportation Improvement Program	Delete	
Progress in retrofitting urban buses with new emission controls	Delete	As time goes on, replacement or rehabilitated buses will use cleaner technologies (e.g., built-in filters) and/or fuels, and the need for retrofits will diminish.
Development of new episodic controls on Spare the Air days	Delete	
Progress in funding bicycle and pedestrian projects	Delete	
NEW: Implementation status of federal and state Transportation Control Measures		
NEW: Periodic updates of motor vehicle emission inventories as part of federal and state planning processes		
NEW: Periodic assessments of the conformity of the Bay Area Transportation Improvement Program and Regional Transportation Plan with the transportation emission "budgets" in the federal air quality plan (or "SIP")		New control strategies implemented at state and regional level will be needed to address criteria pollutants

Existing Measure	Suggested Action	Reasons for Action
<b>EFFICIENT FREIGHT TRAVEL: Moving Goods to Market</b>		
Identification of key freight projects and associated funding	Modify: Identification of key freight projects and associated funding <b>including private sector funding.</b>	To include major private sector investments in the freight network.
Development of a regional truck network on local arterials	Delete	
Inclusion of a regional air cargo plan element in the next Regional Airport System Planning Analysis	No Change	
NEW: Progress in implementing priority freight projects	New measure; priority projects will be identified as part of MTC's efforts to secure Proposition 1B Trade Corridors funding	New measure to track implementation of priority infrastructure improvements
NEW: Progress in implementing new ITS or operational programs to improve efficiency of goods movement and/or environmental impact of goods movement	New measure	Operating efficiencies is a critical component of goods movement within the congested and developed region. Advances in technology are leading to new operating and ITS initiatives that the region should consider.

**Report on  
Transportation 2030 Goals' Key Measures of Progress**

**April 2007**



**METROPOLITAN  
TRANSPORTATION  
COMMISSION**

Joseph P. Bort MetroCenter  
101 Eighth Street  
Oakland, CA 94607-4700  
PHONE 510.817.5700  
TTY/TDD 510.817.5769  
FAX 510.817.5848  
WEB [www.mtc.ca.gov](http://www.mtc.ca.gov)

## **MTC PROJECT STAFF**

Doug Kimsey  
**Manager, Planning**

**Project Managers**  
Carolyn Clevenger  
Raymond Kan

**Project Staff**  
Christina Atienza  
Catalina Alvarado  
Marjorie Blackwell  
Harold Brazil  
Sean Co  
James Corless  
Shauna Callow  
Ben Espinosa  
Jeff Georgevich  
Pierce Gould  
Doug Johnson  
Lisa Klein  
Therese Knudsen  
Carol Kuester  
Peter Lee  
Jaime Maldonado  
Ben McKeever  
Ashley Nguyen  
Raymond Odunlami  
Nancy Okasaki  
Anne Richman  
Theresa Rommell  
Rupinder Singh  
Danielle Stanilaus  
Sri Srinivasan  
Sui Tan  
Glen Tepke  
Ursula Vogler



## *Report on Transportation 2030 Goals' Key Measures of Progress*

### INTRODUCTION

Six goals were adopted in the Transportation 2030 Plan – safety, reliability, access, livable communities, clean air, and efficient freight travel. For each goal, key objectives and measures of progress were identified. The key measures of progress are meant to help MTC evaluate the degree to which its actions, guided by the policies developed in Transportation 2030 Plan, have advanced the plan's goals, and to provide insight as we move forward with the 2009 Regional Transportation Plan (RTP). MTC committed to reporting on these key measures of progress as part of the RTP update.

This report documents progress made in these key measures between the base year, roughly the time of the adoption of the Transportation 2030 Plan (2004), and now, using the most recent data available (typically 2005 or 2006). These measures will either be carried over into the next RTP, modified, or deleted depending on their effectiveness in measuring progress, availability of data, and consistency with the goals and objectives developed for the 2009 RTP.

**Table 1. Transportation 2030 Key Measures of Progress**

#### **Goal**

#### **SAFETY: A Safe and Well-Maintained System**

##### **Objective**

Reduce injuries and fatalities for all modes
Be prepared for future transportation emergencies resulting from natural disasters and security threats
Reduce long term transportation repair costs through timely replacement of assets
Save consumers repair costs due to poor road conditions

##### **Key Measure**

Number of injuries and fatalities at safety "hot spots"
Number of injuries and fatalities
Pavement condition index (freeways and roadways)
Average age of transit fleet
Progress in completing bridge seismic retrofit program

#### **Goal**

#### **RELIABILITY: A Reliable Commute**

##### **Objective**

Provide travel options that are responsive to individual preferences for time, cost, convenience and trip reliability
Increase the number of on-time trips
Improve connections between transit systems and between freeway segments
Improve information on travel conditions and options
Make cost-effective use of new technologies to support objectives

##### **Key Measure**

Capacity added to the MTS
Levels of service in congested corridors
Progress with freeway ramp meters and traffic signal retiming
On-time transit performance
Effectiveness of incident management strategies
New transit connectivity projects
Progress in improving traveler information

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Goal**

#### **ACCESS: Access to Mobility**

##### **Objective**

Identify barriers, such as gaps in service, affordability, and safety
Improve delivery of services by coordinating with a range of agencies
Secure adequate resources to respond to lifeline mobility needs

##### **Key Measure**

Amount of lifeline transportation service provided
Progress in implementing transportation programs for older adults
Progress in completing community-based plans
MTC and transit operator Title VI reports

### **Goal**

#### **LIVABLE COMMUNITIES: A Region of Vibrant Communities**

##### **Objective**

Create incentives to encourage transit-oriented development around regional transit systems and mixed-use development elsewhere
Create new and safer ways to get around within communities by fostering walking and biking and connecting communities to transit
Partner with local communities in developing transportation approaches that enhance community vitality for neighborhoods and retail centers

##### **Key Measure**

Number of TLC projects completed
Number of new transit-oriented development projects assisted with HIP
Number of new mixed-use development projects assisted with HIP
Annual results of T-Plus program

### **Goal**

#### **CLEAN AIR: Clearing the Skies**

##### **Objective**

Achieve additional reductions in motor vehicle emissions through effective transportation control measures
Working with the BAAQMD, develop new episodic control strategies for predicted high-ozone days
Help reduce particulate matter from buses and other heavy duty vehicles
Promote non-motorized travel to reduce auto trips

##### **Key Measure**

Periodic analysis of consistency between T-2030, TIP and federal air quality plan
Progress in retrofitting urban buses
Development of new episodic controls on Spare the Air days
Progress in funding bicycle and pedestrian projects

### **Goal**

#### **EFFICIENT FREIGHT TRAVEL: Moving Goods to Market**

##### **Objective**

Identify key improvements in the surface transportation system where public investment can help the freight industry
Identify long-term capacity issues associated with cargo movement through airports and seaports
Collaborate with the private sector to best leverage both public and private financial resources to improve freight-related infrastructure

##### **Key Measure**

Identification of key freight projects and associated funding
Development of a regional truck network on local arterials
Inclusion of a regional air cargo plan element in the next RASP analysis

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Goal**

### **SAFETY: A Safe and Well-Maintained System**

### **Key Measures of Progress:**

#### **Number of injuries and fatalities at identified safety “hotspots”**

- In terms of an overall trend from 2004 to 2005, the last year for which data is available, the number of collisions involving fatalities went up slightly by three percent, and those involving injuries went down slightly by one percent.


**Table 1: Injury and Fatal Collisions in the Bay Area**

	2004	2005	<b>Percent Change 2004-2005</b>
Injury Collisions	33,524	33,185	-1%
Fatal Collisions	426	438	3%
Total Injury and Fatal Collisions	33,950	33,623	-1%

Source: Metropolitan Transportation Commission

- Taken together, the number of collisions involving fatalities and injuries decreased one percent from 2004 to 2005. Alameda and Santa Clara counties had the highest number of fatal and injury collisions in both 2004 and 2005. These counties also have the highest number of centerline road miles, as well as some of the worst congestion in the Bay Area.

**Chart 1: Injury and Fatal Collisions by Bay Area County, 2005**



Source: California Highway Patrol, California Department of Finance  
Population from DOF Form E-1, as of January 1, 2006

- The number of injuries and fatalities at identified safety “hotspots” is not currently tracked. An initial screening of a handful of the region’s large and busy intersections

## Report on Transportation 2030 Goals' Key Measures of Progress


found that incidents at these intersections accounted for less than one percent of overall incidents.

### Pavement Condition Index (PCI)

#### State owned roadways<sup>1</sup>

- Pavement condition deteriorated on state highways in the Bay Area in 2005, as the share of roads with no distress slipped five percentage points to 68 percent, and the portion showing major structural distresses rose five percentage points to 25 percent.
- At 68 percent, the share of roads with no distress is at its lowest point in the last five years. At the other end of the scale, the percentage of roadway miles showing major structural distress — 25 percent — is at its highest point in five years. Fully one-quarter of the lane-miles on Bay Area state highways now show signs of serious damage.

**Chart 2: Pavement Conditions for Bay Area State Highways, 2001 - 2005**




Source: Caltrans

#### Local streets and roads

- Between 2004 and 2006, the percentage of local streets and roads in “Very Good or better” condition rose from 44 percent to 48 percent, while at the other end of the spectrum, those in “Poor or worse” condition remained steady at 17 percent. In 2005 the PCI for the Bay Area increased between from 62, on a scale of 100, to 64. Only Marin and Napa showed decreases in PCI, with one and four point drops respectively.

<sup>1</sup> State-owned roadways are commonly called state highways and include freeways, rural highways (such as Route 1 along the Pacific Coast, Route 29 in Napa and Route 116 in Sonoma) and state-owned urban and suburban arterials (such as San Pablo Avenue in Alameda and Contra Costa counties and Skyline Boulevard in San Mateo County).

**Chart 3: Pavement Condition of Local Streets and Roads**



Source: Metropolitan Transportation Commission

- The current funding required to bring all local streets and roads (41,167 lane miles) in the Bay Area up to a “very good” or “excellent” ratings is \$6.4 billion.
- While the actual pavement repair that was accomplished using the Transportation 2030 Plan discretionary funding for local streets and roads is a modest amount (\$159 million or 2% of the existing backlog), progress over the last few years in the areas of regional policy, guidelines and programs has helped jurisdictions make the most out of limited resources. Project cost effectiveness as well as having an effective preventative maintenance plan in place are now both requirements for receiving Transportation 2030 maintenance funds.
- The Local Streets and Roads Committee elected to fund the Pavement Technical Assistance Program (PTAP) that was one of the regional programs to be sunsetted in FY 2008-09 per the Transportation 2030 plan. The annual cost of the PTAP program is roughly equivalent to reconstructing one lane mile of pavement (\$730,000).

#### **Average age of transit fleet**

- Overall, the Bay Area’s transit fleet was 0.2 years younger between 2003 and 2005, representing a 2.3 percent decrease in the average age of the vehicle. The fleet also became smaller over that period, with nearly 300 fewer standard buses in service.
- Buses, including regular, articulated and trolley buses, got younger, with regular and articulated buses roughly half a year younger and trolley buses over a year and a half younger.
- Heavy rail passenger cars got 2 years older on average, while light rail vehicles got nearly 2 years younger over the same period. Commuter rail vehicles remained roughly the same age, at an average age of 17 years, while the active fleet of commuter rail vehicles increased over 19 percent.

*Report on Transportation 2030 Goals' Key Measures of Progress*

**Table 2: Change in Average Transit Vehicle Age**

Vehicle Type	2003		2005		Change	
	Total Active Fleet*	Average Age (Years)	Total Active Fleet*	Average Age (Years)	Total Active Fleet*	Average Age (Years)
<b>Regional Totals</b>						
Vans/Autos	167	2.9	251	4.3	84	1.5
Buses	2,759	7.4	2,472	6.8	-287	-0.6
Articulated buses	170	5.8	251	5.4	81	-0.4
Trolleybuses	343	9.8	362	8.1	19	-1.7
Vintage Trolley	0		2	88.5	2	
Cable cars	40	93.8	40	95.8	0	2.0
Light rail vehicles (Streetcars)	273	15.5	281	13.6	8	-1.9
Heavy rail passenger cars	668	5.7	667	7.7	-1	2.0
Commuter rail passenger coaches	124	17.2	148	17.0	24	-0.2
Ferryboats	9	19.1	10	15.8	1	-3.3
Total All Vehicles	4,553	8.6	4,484	8.4	-69	-0.2

Source: National Transit Database; includes only vehicles owned by transit agencies

Distance between service calls

The Bay Area's rail operators reported a major improvement in a key measure of reliability in 2004-05. The average distance traveled between service calls for rail increased 30 percent, to 7,890 miles. Meanwhile, the average distance traveled between bus service calls decreased 7 percent, in large part due to difficulties operators had with new technology buses. A service call occurs when a bus or train requires repair and cannot complete scheduled service.

**Table 3: Average Miles Between Service Calls**

Operator	Fiscal Year 2003-04	Fiscal Year 2004-05	Percent Change
<b>Bus</b>			
Muni	2,100	1,950	-7%
VTa	4,500	4,460	-1%
AC Transit	4,680	5,120	9%
Golden Gate Transit	15,920	7,940	-50%
SamTrans	17,090	19,020	11%
<i>Weighted Average (weighted by revenue service miles)</i>	6,130	5,680	-7%
<b>Rail</b>			
Muni	2,400	2,340	-2%
VTa	15,950	22,860	43%
BART	6,940	8,610	24%
<i>Weighted Average (weighted by revenue service miles)</i>	6,060	7,890	30%

Source: National Transit Database FY2004-05 operator reports.

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Progress in completing bridge seismic retrofit program**

#### State bridges

- Since the last RTP, the Richmond-San Rafael Bridge seismic retrofit project was completed in 2005, at a total budgeted project cost of \$825 million.
- Currently, the last of five bridges in the \$8.7 billion Toll Bridge Seismic Retrofit Program to be fully retrofitted is the San Francisco-Oakland Bay Bridge. Work was completed on the West Spans of the Bay Bridge in 2004, at a totaled budgeted project cost of \$308 million.
- The Bay Area Toll Authority and Caltrans are currently reexamining the Dumbarton and Antioch bridges to determine the future retrofit needs of those structures, if any. These two remaining bridges were not included as part of the Toll Bridge Seismic Retrofit Program.

**Table 4: Status of Seismic Retrofit Program**

Bridge	Status	
	2004	2006
San Francisco-Oakland	In progress	In progress
Richmond-San Rafael	In progress	Completed
San Mateo-Hayward	Completed	Completed
Benicia Martinez	Completed	Completed
Carquinez	Completed	Completed

Source: Bay Area Toll Authority

#### Local bridges

- The estimated cost of seismic needs for local bridges in Bay Area was approximately \$57 million in 2004. Seismic repairs on local bridges are funded primarily through the Seismic Safety Retrofit Program. In 2003, the state suspended funding for the program. This, combined with environmental delays on previously funded projects, delayed the Local Seismic Retrofit Program.
- Of the 73 bridges in the program in 2003, twelve have been retrofitted and seven are currently in construction. Forty-eight bridges are in design for seismic retrofit, up from thirty-nine in 2003.

**Table 5: Local Bridges Seismic Retrofit Program**

County	In Strategy		In Design		In Construction		Total	
	2003	2006	2003	2006	2003	2006	2003	2006
Alameda	0	0	20	19	6	0	26	19
Contra Costa	3	0	0	5	10	1	13	6
Marin	0	0	2	2	2	0	4	2
Napa	0	0	0	0	0	0	0	0
San Francisco	0	0	1	2	0	1	1	3
San Mateo	0	0	3	5	1	1	4	6
Santa Clara	6	5	6	4	4	1	16	10
Solano	1	1	0	0	1	1	2	2
Sonoma	0	0	7	11	0	2	7	13
<b>TOTAL</b>	<b>10</b>	<b>6</b>	<b>39</b>	<b>48</b>	<b>24</b>	<b>7</b>	<b>73</b>	<b>61</b>

Source: Metropolitan Transportation Commission

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Goal**

#### **RELIABILITY: A Reliable Commute**

#### **Key Measures of Progress:**

#### **Capacity added to the regional transportation system**

##### Roadways

- Between 2000 and 2006, MTC's regional freeway network grew by transportation system model shows an overall increase of approximately 320 miles. Of that, just roughly 100 miles were additions to the HOV network.
- In 2004, there were 323 lane-miles in the HOV system. In 2005, that grew to 340 lane-miles, with new additions on State Route 87, I-880 and the I-880/237 connector in Santa Clara County and two new additions to the I-680 network in Contra Costa County.

**Table 1: Regional Transportation Network Lane Miles**

Use	Year 2000	Year 2006	Differences 2000-2006
Mixed Flow	34,651	34,873	222
HOV2	289	391	102
HOV3+	39	37	(2)
Truck	162	162	0
<b>Total</b>	<b>35,141</b>	<b>35,463</b>	<b>322</b>

Source: Metropolitan Transportation Commission

##### Transit network

- The number of passenger seat miles in the region's transit network decreased by about 3 percent between 2004 and 2006. In 2004, there were 3,447,000 passenger seat miles. By 2006, this had decreased to 3,356,000 largely due to service cuts as operators adjusted service to budget constraints.

#### **Levels of Service in the congested corridors**

- Since the last RTP, congestion has worsened in the Bay Area, and the most congested corridors fared no better than the region as a whole.
- Half of the most congested locations are already connected to the region's HOV network, with the second and third most congested locations, both on I-580, funded to join the network in 2013 and 2010. State Route 4 will also see new carpool lanes in construction in 2008, and an HOV gap closure on US-101 between State Route 1 and I-580 in Marin County is currently under construction.
- Most all of the congested corridors do have transit options available, though in several cases buses currently share lanes with other traffic and are subject to the same delays. With completion of the HOV segments listed above, buses on all but one of the congestion segments will be able to bypass congestion. Current bus service on State Routes 4 and 92 does not meet the 15-minute headway criteria for high-frequency service.



## Report on Transportation 2030 Goals' Key Measures of Progress

- In contrast, the region is not making full use of freeway ramp metering to help manage congestion and improve travel time reliability. Ramp metering is in operation in just three of the congested segments.

**Table 2: Travel in the Region's Most Congested Locations**

Most Congested Locations in 2004	Average Daily Freeway Delay (vehicle hours)			Reliable Travel Options (1)			
	2004	2005	2005 Rank	HOV Lanes	Freeway Ramp Metering	High-Frequency Transit in Preferred Right-of-Way (2)	
1 I-80, westbound, AM - Alameda/Contra Costa, SR 4 to Bay Bridge metering lights	10,080	10,930	1	+	-	+	Bus BART
2 I-580, westbound, AM - Alameda County, North Flynn Rd to Airway Blvd	5,120	5,830	3	-*	o	-	Frequent bus; no HOV
3 I-580, eastbound, PM - Alameda County, Hopyard Rd to west of El Charro Rd	4,320	6,100	2	-*	o	-	Frequent bus; no HOV
4 US 101, northbound and I-80, eastbound PM - San Francisco, Cesar Chavez St to west end of Bay Bridge	3,840	5,140	4	-	-	-	Frequent bus; no HOV
5 SR 92, eastbound, PM - Alameda County, Clawiter Rd to I-880 interchange	3,760	3,880	7	+	-	-	Bus does not meet frequency threshold
6 SR 4, westbound, AM - Contra Costa County, Lone Tree Way to west of Loveridge	3,600	4,000	6	-*	-	-	Bus does not meet frequency threshold
7 US 101, southbound, AM - Marin County, North of SR 37 to I-580	3,110	4,490	5	+	-	+	Bus
8 US 101, northbound, PM - Marin County, SR 1 to I-580	2,680	3,690	9	o*	-	o	Bus
9 US 101, northbound, AM - Santa Clara County, I-280 to north of Trimble Rd	2,560	2,320	14	+	+	+	Caltrain Bus
10 I-80, eastbound, PM - San Francisco and Alameda counties, West of Treasure Island to east of Powell Street	2,430	3,120	10	o	n/a	+	BART Bus
<b>New to Most Congested List in 2005</b>							
SR 4, eastbound, PM - Contra Costa County, West of Bailey Rd to A Street/Lone Tree Way	2,340	3,780	8	o*	-	-	Bus does not meet frequency threshold

Sources: MTC and Caltrans, Bay Area Transportation State of the System 2004 and 2006, Caltrans, Bay Area HOV Lanes 2004 and 2005 reports.

Notes: (1) + Indicates full coverage over the congested segment; o indicates partial coverage; - indicates no coverage  
(2) Service at least every 15 minutes. Preferred right-of-way includes HOV lanes for buses.

\* HOV lanes under construction or fully funded

### Progress with freeway ramp meters and traffic signal retiming

#### Ramp meters

- In late 2004, 205 ramps were metered in the Bay Area. Currently, that number has increased to 231, with 25 new ramp meters activated in the first two months of 2007. The 231-metered ramps represent 23 percent of the 1,016 ramps in the Bay Area.

**Table 3: Ramp Meters**

	2004	2006	Total New Ramps
<b>Number of operational ramp meters</b>	<b>205</b>	<b>231</b>	<b>26</b>

Source: Caltrans, Metropolitan Transportation Commission

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### Traffic signal retiming

- In 2005, MTC completed 11 projects in the Regional Signal Timing Program. Combined with those projects completed in 2004, the Regional Signal Timing Program has saved drivers nearly 500,000 hours per year, reducing fuel consumption by over 650,000 gallons and emissions by nearly 46 tons per year.

**Table 2: Traffic Signal Program**

<b>Regional Signal Timing Program Performance</b>	<b>2004 Cycle</b>	<b>2005 Cycle</b>	<b>Cumulative</b>
Total Cost (2005\$)	\$744,690	\$1,076,380	\$1,821,070
Number of Projects Completed	15	11	26
Number of Signals Retimed	340	449	789
Benefit Period (5 years)	2004-2009	2005-2010	2004-2010
Benefits			
Travel Time Savings (hours/year)	247,200	339,000	488,500
Fuel Consumption Savings (gallons/year)	330,600	451,200	651,500
Emissions Reductions (tons/year, with CO / without CO)	23.5 / 4.0	31.6 / 5.9	45.9 / 8.2

Notes: 1) Cumulative benefits are not additive due to the different benefit periods for each Cycle. 2) Emissions are ROG, NOx, PM10, and CO.

Sources: Field-measured travel time and delay studies, Caltrans, California Life-Cycle Benefit/Cost Analysis Model and Technical Supplement to the User's Guide, 1999. MTC, Travel Demand Models for the San Francisco Bay Area (BAYCAST-90) Technical Summary, 1997. US Dept of Labor, Bureau of Labor Statistics

### **On time transit performance**

- Overall, the region's major transit providers have had mixed results in terms of on time performance since 2004, with only three services meeting their on time goals.
- Rail systems reported much higher on time performance than bus systems, which are often stuck using the same congested roadways as other passenger vehicles. VTA, Caltrain and BART continue to report the best on-time performances, with all three agencies operating on-schedule more than 90 percent of the time.
- The on-time arrival rate for San Francisco Muni, which operates under some of the most challenging conditions in the Bay Area, significantly lags behind other systems. Muni has pledged to focus on improvements and three of four Muni modes monitored posted significantly better on-time arrivals in FY 2004-05.

## Report on Transportation 2030 Goals' Key Measures of Progress

**Table 3: On Time Performance of Major Transit Operators**

Operator	2003-04*	2004-05*	FY04-05 Goal
<b>Buses</b>			
VTA	97%	94%	95%
SamTrans	88%	91%	85%
Golden Gate Transit	82%	81%	90%
Muni (motor bus)	69%	73%	85%
Muni (electric trolley bus)	72%	70%	85%
AC Transit	66%	67%	90%
<b>Rail</b>			
VTA	96%	97%	95%
Caltrain	92%	97%	95%
BART	93%	92%	95%
Muni	66%	77%	85%

Sources: AC Transit, Golden Gate Transit, Muni, SamTrans, Valley Transportation Authority, Caltrain, BART.

### Effectiveness of incident management strategies

- MTC operates two incident management programs: MTC SAFE Freeway Service Patrol (FSP) and Call Box Programs. Between 2004 and 2006, there was a slight decline (less than 3%) in the total number of assists, but customer satisfaction remained very high.
- In addition, there was improved call service, with the monthly delay in call answering dropping from just over 9 seconds to 8 seconds.

**Table 4: Incident Management Programs**

<u>Measure</u>	<u>2004</u>	<u>2006</u>
<b>Freeway Service Patrol</b>		
Centerline miles covered	440	460
Total number of assists	135,700	132,600
Assist rate (# of assists per hour per truck)	0.93	0.86
Customer service rating (% of motorist surveys marked "excellent")	94.8%	95.9%
Avg. motorist wait time	9.4 min	9.4 min
<b>Call Box</b>		
Monthly delay in call answering	9.2 sec	8.0 sec

Source: Metropolitan Transportation Commission

### New transit connectivity projects

- The Transit Connectivity Plan, adopted by the Commission in April 2006 and received funds for its implementation in July 2006, recommends improvements in the areas of wayfinding signage, transit information display cases (printed transit information) and real-time transit information displays at key regional transit hubs identified in the Plan.

## ***Report on Transportation 2030 Goals' Key Measures of Progress***

- Since adoption, MTC has worked with transit operators to review each of the 24 regional transit hubs (including three airports) for compliance with the Plan recommendations and to identify potential improvements.
- Regional coordination of transit connectivity activities is proceeding under MTC's Transit Coordination and Information Section, in collaboration with transit operators, will be responsible for implementing the Plan's recommendations.
- Progress going forward will be measured based on implementation of wayfinding signage improvements, transit information, and real time transit information at the regional transportation hubs.

### **Progress in improving traveler information**

- Between 2004 and 2006, MTC made significant progress in improving the availability of traveling information. Fully launched in March 2004, 511.org is a free phone and Web service that consolidates Bay Area transportation information into a one-stop resource. 511 provides up-to-the-minute information on traffic conditions, incidents and driving times, schedule, route and fare information for the Bay Area's public transportation services, instant carpool and vanpool referrals, bicycling information and more.
- Between 2004 and 2006, there was a 57 percent increase in calls to 511, a 167 percent increase in user sessions on the website, and a more than doubling of freeway miles covered.

**Table 5: Regional 511 Coverage and Usage**

<b><u>Measure</u></b>	<b><u>2004*</u></b>	<b><u>2006</u></b>
Phone calls to 511	3,296,120	5,180,583
User sessions on 511.org	6,210,029	16,555,793
Freeway miles covered	280 miles	585 miles
Percentage of freeway network covered	45%	94%

\* All of 511.org was not launched until March 2004, so this data only reflects Mar-Dec 04.

Source: Metropolitan Transportation Commission

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Goal**

#### **ACCESS: Access to Mobility**

#### **Key Measures of Progress:**

##### **Amount of Lifeline transportation service provided**

- MTC remains committed to improving transportation choices for Bay Area residents. As identified in Transportation 2030, MTC is dedicating \$216 million to a Lifeline Transportation Program over the next 25 years. MTC allocated an additional \$18 million to launch the program in December 2006 before these new funds become available. MTC staff recently released for comment a regional transit proposal that allocates new funds from Proposition 1B over a ten-year period. The final allocation will be determined by mid-2007.

**Table 1. Summary of Lifeline Funding (FY2006 – FY2008)**

	Total (CMAQ + STA + JARC)
Lifeline Program Revenue	\$18,232,956
Total Proposed Programming	\$14,692,239
Unprogrammed Balance	\$ 3,540,717

(Source: MTC Staff)

**Table 2. Breakdown of Funding for Lifeline Program**

Lifeline Projects Categories	Percent of Total Funding
Fixed-Route Transit	33%
Transit/Bicycle/Pedestrian Amenities	27%
Shuttles/Demand Response	15%
Auto Programs (loans, carsharing)	11%
Fare Assistance	7%
Children's Shuttle	4%
Guaranteed Ride Home	2%
Marketing/Outreach for service	1%

(Source: MTC Staff)

- The Low Income Flexible Transportation (LIFT) Program began in 2000 and has funded a wide range of transportation services, from new fixed public transit to children's shuttles, and even auto-loan programs. MTC programmed the third cycle of the LIFT program at the end of 2004. No additional funds have been committed to LIFT beyond the current cycle.

**Table 3. Summary of LIFT Funding Grants**

Cycle	Total LIFT Grant
Funding Cycle 1	\$5,614,670
Funding Cycle 2	\$5,652,623
Funding Cycle 3	\$2,755,924

(Source: MTC Staff)

## *Report on Transportation 2030 Goals' Key Measures of Progress*

**Table 4. Breakdown of Funding for LIFT Program**

LIFT Projects Categories	Percent of Total Funding
Fixed-Route Transit	41%
Shuttles/Demand Response	20%
Fare Assistance	14%
Children's Shuttle	13%
Auto Programs (loans, carsharing)	6%
Mobility Manager	5%
Transit/Bicycle/Pedestrian Amenities	1%

(Source: MTC Staff)

### **Progress in implementing transportation programs for older adults**

- As required by SAFETEA-LU, the Coordinated Public Transit-Human Services Plan is MTC's latest planning effort to assess the needs of older adults, as well as disabled and low-income residents in the Bay Area, and to develop coordinated regional solutions. The Coordinated Plan will be completed in May 2007.
- MTC and its Elderly and Disabled Advisory Committee (EDAC) continue to support initiatives that address a rapidly aging region. In January 2006, MTC and EDAC hosted *A Regional Summit on Older Drivers* to educate senior advocates and service providers on helping older drivers stay sharp behind the wheel and, if necessary, make the transition from driving to other options. A DVD of the summit's proceedings is currently in post-production, and once completed it will be distributed to all summit participants as well as other associated organizations and groups.
- In May 2005, MTC convened a special forum – *Mobility Matters: Taxis and Their Role in Bridging the Accessibility Gap* – to allow the taxi industry, transit agencies, seniors groups, community-based organizations, social service agencies, and others to share information about innovative taxi programs. In addition to older adults, many of these ideas could bridge accessibility gaps for people with disabilities and low-income residents.

### **Progress in completing community-based plans**

- MTC is making steady progress in completing Community-Based Transportation Plans (CBTP) for those economically disadvantaged communities identified in the 2001 Lifeline Transportation Network Report. Five CBTPs were completed by early 2005. Six additional CBTPs have been completed to date, with two more to be completed by Spring 2007 (Mission District and Santa Rosa).

## *Report on Transportation 2030 Goals' Key Measures of Progress*

**Table 5. Status of Community-Based Transportation Plans**

Completed CBTPs	<i>Completed by early 2005</i> <ul style="list-style-type: none"> <li>Richmond/ North Richmond/ Old Town San Pablo</li> <li>Ashland/ Cherryland/ South Hayward</li> <li>City of Napa</li> <li>East Palo Alto</li> <li>Dixon</li> </ul>	<i>Completed by Spring 2007</i> <ul style="list-style-type: none"> <li>West Oakland</li> <li>Monument Corridor (Concord)</li> <li>Gilroy</li> <li>Canal District of San Rafael</li> <li>Pittsburg/Bay Point</li> <li>Civic Center (San Francisco)</li> </ul>
CBTPs Underway	<ul style="list-style-type: none"> <li>Mission District (San Francisco)</li> <li>Santa Rosa (west of Highway 101)</li> <li>Cordelia</li> </ul>	<ul style="list-style-type: none"> <li>Berkeley/West Berkeley</li> <li>East Oakland</li> <li>Marin City</li> </ul>
Remaining CBTPs	<ul style="list-style-type: none"> <li>East San Jose</li> <li>Martinez</li> <li>Bayview Hunters Point</li> </ul>	<ul style="list-style-type: none"> <li>Milpitas</li> <li>Daly City (San Bruno)</li> <li>Vallejo</li> </ul>

(Source: MTC Staff)

### **MTC and transit operator Title VI reports**

- Title VI Compliance Reports provide information and analyses bearing on MTC and transit operators' compliance with Title VI of the 1964 Civil Rights Act regarding nondiscriminatory delivery of services and benefits under federally-funded programs or activities. The report covers the preceding three fiscal years.
- MTC submitted its latest triennial Title VI Compliance Report in 2006, which covers the years 2004, 2005, and 2006. The next update is expected to be prepared in 2009. The major transit operators have all either completed or are currently updating their Title VI reports for the FTA directly.

**Table 6. Transit Operator Title VI Reports Status**

Transit Operator	Year of Completion of Current Title VI Report	Year of Next Update
AC Transit	2003	2007 (covering 2004-6)
BART	2004	2007
Caltrain	2006	2009
Golden Gate Transit	2006	2009
Muni	2004	2007
SamTrans	2004	2007
VTA	2005	2008

(Source: Transit Operators)

- Additionally, MTC is funding and administering a Transit Passenger Demographic Survey of 22 Bay Area transit operators. The survey asks transit customers about their trip patterns, trip frequency, access to automobiles, race, and income. The final consultant report will be submitted to MTC by July 2007. Results from this survey will provide critical information to MTC staff as they continue to tackle access issues for the region's diverse residents.

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Goal**

### **LIVABLE COMMUNITIES: A Region of Vibrant Communities**

### **Key Measures of Progress:**

#### **Number of TLC projects completed**

- MTC launched the TLC program in 1998 to fund local planning studies and capital projects to encourage more vital and livable neighborhoods and communities. Through the Transportation 2030 Plan, MTC created the County TLC/HIP program, which provides over \$9 million per year to counties to create customized TLC, HIP, or combined TLC/HIP programs in their county. There is no county TLC planning program.

**Table 1. Status of TLC Projects**

	Planning Projects Completed or Underway as of Dec. 2004	Planning Projects Completed or Underway as of March 2007	Capital Projects Completed or Underway as of Dec. 2004	Capital Projects Completed or Underway as of March 2007
Regional TLC	60	68	73	82
County TLC	N/A	N/A	0	12
Regional and County TLC	N/A	N/A	0	2
Total	60	68	73	96

(Source: MTC Staff)

#### **Number of new Transit Oriented Development projects assisted with HIP, and Number of new mixed use development projects assisted with HIP**

- MTC expanded the TLC portfolio in 2000 to include the Housing Incentive Program (HIP), which provides capital funding assistance to local governments and developers to construct dense housing near transit stops. Most county TLC/HIP funds are used for TLC projects. At this time only San Mateo and Marin counties have established a county HIP program.

**Table 2. Status of HIP Projects**

	TOD Housing and Mixed-Use Projects Assisted* as of Dec. 2004	TOD Housing and Mixed-Use Projects Assisted as of March 2007**
Regional HIP	15	24
County HIP	N/A	3
Regional and County HIP	N/A	0
Total	15	27

(Source: MTC Staff)

\* Staff have combined the mixed-use and TOD HIP grant categories into a single measure because by definition all HIP projects are transit-oriented, whereas mixed-use is not a critical criterion for HIP grants.

\*\* The 2004/5 cycle of HIP projects have until June 2007 to receive building permits and in turn the HIP grants. Since a number of new projects are expected to meet this deadline, these figures will be updated.



## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Annual results of T-PLUS program**

- To further integrate transportation and local land use planning, MTC established the Transportation Planning and Land Use Solutions (T-PLUS) program in 2005. T-PLUS provides \$150,000 to each CMA for each of three years to build planning capacity focusing on TLC/HIP, TOD, and traffic mitigation programs. MTC staff is currently preparing the annual evaluation of the T-PLUS program. The report will go to the Planning Committee for review in May 2007. At that time, the Committee will determine whether to extend the program, and if so, for how long. In general, the T-PLUS program has:
  - Created capacity for implementation of regional goals and programs (e.g. county TLC)
  - Enabled local planning staff to participate in or lead numerous smart growth planning studies
  - Enabled some staff to develop toolkits specifically related to smart growth planning and TOD
  - Enabled staff-level support for relevant Resolution 3434 (see next measure) planning activities in their jurisdictions
  - Enabled some CMAs to improve their modeling and GIS capabilities related to land use and transit planning
  - Enabled CMAs to use T-PLUS funds to add staff to accomplish the tasks outlined above

### **NEW: TOD Policy Implementation**

- The \$11.8 billion Regional Transit Expansion Program that MTC adopted as Resolution 3434 in 2001 was accompanied by a strong directive to develop a policy that would condition the allocation of regional discretionary funds for transit expansion projects on supportive local land use plans and policies. In 2005, MTC adopted the Resolution 3434 Transit-Oriented Development (TOD) Policy. Today, 19 of 41 stations have station area plans completed or underway, compared to only seven stations back in 2004. In the last three years, planning had begun for 12 stations, eight of which are funded by MTC.

**Table 3. New Station Area Plans Underway or Completed since 2004**

Resolution 3434 Corridor	Station Area	Plan Fund Source
Dumbarton Rail	Menlo Park	MTC
Dumbarton Rail	Redwood City	City
e-BART	Pittsburg/RR Avenue	MTC
e-BART	Antioch/Fairgrounds	MTC/BART
e-BART	Antioch/Hillcrest	MTC/BART
e-BART	Oakley/Neroly Road	MTC/BART
Ferries	Richmond	WTA/DCE
Ferries	Alameda	MTC
BART to San Jose	Milpitas	City
BART to San Jose	San Jose downtown	City
BART to San Jose	Santa Clara	MTC
SMART	Santa Rosa downtown	MTC

(Source: MTC Staff)

## *Report on Transportation 2030 Goals' Key Measures of Progress*

### **Goal**

#### **CLEAN AIR: Clearing the Skies**

#### **Key Measures of Progress:**

**Periodic analysis of consistency between the Transportation 2030 Plan and Transportation Improvement Program (TIP) and the federal air quality plan (also known as transportation “conformity”).**

- The Federal Highway Administration and Federal Transit Administration approved MTC’s conformity determination for the Transportation 2030 Plan and 2005 TIP Amendment #05-05 on March 17, 2005. Currently, MTC has released the Draft Conformity Analysis of the Amendment to the Transportation 2030 Plan and 2007 TIP Amendment #07-06 for a 30-day public review from March 9, 2007 to April 9, 2007. New funding from Proposition 1B and other fund sources has allowed two new projects to be added to the financially constrained element. Staff has concluded that motor vehicle emissions from these plan amendments are below emissions budgets contained in the federal air quality plan.

**Table 1. 2005 Air Quality Conformity Analysis**

<b>Emissions Budget Comparisons for Ozone</b>				
Year	VOC Budget	Net VOC Emissions	NO <sub>x</sub> Budget	Net NO <sub>x</sub> Emissions
2006	164.0	129.2	270.3	253.2
2007	164.0	119.4	270.3	234.8
2015	164.0	69.6	270.3	125.1
2025	164.0	44.6	270.3	66.8
2030	164.0	37.7	270.3	54.9
<b>Emission Budget Comparisons for Carbon Monoxide</b>				
Year	1998 CO Budget*	CO Emissions		
2006	2,193	1,352.3		
2010 (interpolated)	2,193	1,046.1		
2015	2,193	663.3		
2025	2,193	353.8		
2030	2,193	295.8		

(Source: Transportation Air Quality Conformity Analysis for Transportation 2030 Plan and 2005 Transportation Improvement Program/Amendment #05-05)

\* 1998 Revision to the 1996 Carbon Monoxide Maintenance Plan for 10 Federal Planning Areas

**Report on Transportation 2030 Goals' Key Measures of Progress**

**Table 2. 2007 Air Quality Conformity Analysis**

<b>Emissions Budget Comparisons for Ozone</b>				
Year	VOC Budget	Net VOC Emissions	NO <sub>x</sub> Budget	Net NO <sub>x</sub> Emissions
2006	164.0	126.2	270.3	248.3
2007	164.0	116.0	270.3	229.3
2015	164.0	68.3	270.3	123.0
2025	164.0	44.3	270.3	66.5
2030	164.0	37.9	270.3	55.4
<b>Emission Budget Comparisons for Carbon Monoxide</b>				
Year	2004 CO Budget**	CO Emissions		
2006	1,850	1,320.0		
2007	1,850	1,204.9		
2015	1,850	647.8		
2018 (interpolated)	1,850	558.5		
2025	1,850	350.2		
2030	1,850	297.0		

(Source: Draft Transportation Air Quality Conformity Analysis for Amendment to the Transportation 2030 Plan and 2007 Transportation Improvement Program Amendment 07-06)

\*\* 2004 Revision to the California State Implementation Plan for Carbon Monoxide, Updated Maintenance Plan for 10 Federal Planning Areas

**Progress in retrofitting urban buses with new emission controls**

- In February 2000, the Air Resources Board adopted the Fleet Rule for Transit Agencies and more stringent exhaust emission standards for new Urban Bus engines and vehicles. The Bay Area's transit operators are making progress in retrofitting 1,700 diesel buses with particulate matter filters (which also filter out NO<sub>x</sub>) as part of MTC's Clean Diesel Bus Program. MTC is funding this program with \$14 million in CMAQ plus other local funds.

May 2005: ~23% Retrofitted

March 2007: ~81% Retrofitted

- As new and cleaner buses are procured and replace older buses, or as older buses are rehabilitated with cleaner engines, there will be a lesser need to install diesel particulate filters as "retrofits" to achieve the target fleet emissions reductions.

## ***Report on Transportation 2030 Goals' Key Measures of Progress***

### **Development of new episodic controls on Spare the Air days**

- Since 2005, MTC and the Bay Area Air Quality Management District (Air District) have funded and administered the Spare the Air/ Free Transit program. Planning for the 2007 program is well underway for this summer's ozone season.
- In 2005, the free transit program was limited to the weekday morning commute only. Only one Spare the Air day was declared by the Air District that summer (July 26, 2005). Transit ridership increased by 21,000 rides or 6.7% over a typical weekday. MTC and the Air District estimated the emissions reduction impacts as follows:
- In 2006, the free transit program was expanded to the entire weekday. Six Spare the Air days were declared that summer. The number of transit rides rose by 15% system-wide, equating to 225,000 additional rides per free transit day. MTC and the Air District calculated the following emissions reductions:

**Table 3. Spare the Air/Free Transit Campaign Results**

	NO <sub>x</sub> (tons/day)	ROG (tons/day)	PM-10 (tons/day)
2005 Campaign	1.53	1.48	0.53
2006 Campaign	2.22	2.18	0.85

(Source: Air District)

### **Progress in funding bicycle and pedestrian projects**

- MTC continues to fund an increasing number of important bicycle and pedestrian projects throughout the nine counties using regional discretionary fund sources. In December 2003, the Commission dedicated \$200 million over 25 years for bicycle and pedestrian improvements throughout the Bay Area, including portions of the Regional Bicycle Network. In addition, the TLC/HIP program helps fund bicycle and pedestrian projects.

**Table 4. Status of Bicycle and Pedestrian Projects**

	2004/5	2005/6	2006/7
Number of Funded Projects	104	128	38*
Amount of Funding**	\$19,290,000	\$32,983,000	\$32,402,000

(Source: MTC Staff)

\* Funding for ten of these projects began in previous years. Additional projects are expected to be submitted by local sponsors for funding, including TDA-funded projects, prior to the end of FY 2007.

\*\* MTC's fund sources comprise STP, CMAQ, STIP, TDA, and RM2 funds

**Goal: EFFICIENT FREIGHT TRAVEL: Moving Goods to Market**

**Key Measures of Progress:**

**Identification of key freight projects and associated funding**

- The Regional Goods Movement Study identified two high priority interregional goods movement corridors:
  - 1) I-80 from the Bay Area through Sacramento - known as the Central Corridor; and
  - 2) I-580/238/880 from the Bay Area through the Central Valley– known as the Altamont Corridor.
- Investment in these corridors focuses on the dual goods movement issues of:
  - (1) ensuring the future viability and growth of the Port of Oakland as a trade gateway for both imports and exports; and
  - (2) the economic interconnections of the Sacramento and San Joaquin Valley regions with the Bay Area through interregional goods distribution corridors.
- Recognizing the importance of these two issues, MTC has had discussions with various partner agencies, including the Port of Oakland, the Bay Area and Contra Costa Councils, the East Bay Economic Development Alliance, the Alameda CMA, the San Joaquin, Sacramento and Stanislaus Councils of Governments, and others, to begin identifying key goods movement projects that would serve both corridors, which would be collectively called the Northern California Trade Corridor.
- The Northern California Trade Corridor will be an integrated program designed to meet current and future requirements to move people and goods throughout the state and the nation quickly, reliably and safely, with less highway congestion and pollution.
- The program envisions a combination of rail and highway improvements focused along the two major trade corridors identified above. Although the focus has been the Proposition 1B Infrastructure Bond, future infrastructure needs far exceed the funding available in the bond, and will require corridor-level strategies as the Bay Area looks towards the next federal reauthorization in 2009.
- The private sector is also a key partner in goods movement. MTC is actively working with our partners at the Port of Oakland to engage the Union Pacific and BNSF Railroads in discussions regarding future investments in the freight network.

**Development of a regional truck network on local arterials**

MTC is planning on pursuing this project in FY 2007/08. In addition, the Alameda County Congestion Management Agency recently released a Request for Proposals for a Truck Parking Facility Study to evaluate the demand for truck parking facilities in Alameda County and to conduct a preliminary scan for potential locations based on the results of the demand analysis. This study is scheduled to be completed at the beginning of 2008.

**Inclusion of a regional air cargo plan element in the next Regional Airport System Planning Analysis**

The Regional Airport Planning Committee (RAPC) is an advisory committee of MTC, ABAG and BCDC. One of the committee's charges is to develop a Regional Airport System Plan (RASP), which assesses future air passenger, air cargo and general aviation at the regional level. The last RASP was completed in 2000, and RAPC is currently re-examining the original set of alternative strategies prescribed in the RASP. Air cargo is being considered as part of this evaluation, which is scheduled to be complete in 2009.